

1 **Bridging BIM and building (BBB) for information management in**
2 **construction: The underlying mechanism and implementation**

3 Ke CHEN¹, Weisheng LU²

4 **Abstract**

5 **Purpose**—How to make effective use of building information modeling (BIM) for information
6 management (IM) is a challenging question in the field of construction project and asset
7 management (CPAM). Chen et al. (2015) answered this question by developing a conceptual
8 framework of ‘bridging BIM and building (BBB)’. However, the underlying mechanism
9 through which BBB can truly impact IM remains unclear. The purpose of this paper is thus to
10 demystify the mechanism linking BBB and IM.

11 **Design/methodology/approach**—Drawing upon the IM literature, this study proposes three
12 IM requirements, namely, requirements on information quantity, quality, and accessibility, as
13 significant mediators between BBB and IM. To verify this proposition, a two-year,
14 participatory case study was conducted based on a real-life construction project in which a
15 BBB system was implemented.

16 **Findings**—The results of the case study supported the proposition that by enhancing the
17 information quantity, quality, and accessibility BBB could favorably contribute to IM in
18 construction.

19 **Practical implications**—This paper provides knowledge about system architecture,

¹ Corresponding author, Department of Construction Management, Huazhong University of Science and Technology, Wuhan, China; Department of Real Estate and Construction, The University of Hong Kong, Hong Kong, Email: chenkecm@hust.edu.cn;

² Department of Real Estate and Construction, The University of Hong Kong, Hong Kong, Email: wilsonlu@hku.hk;

20 components, and their linkage in an operable BBB system. It also provides empirical
21 experience about BBB implementation.

22 **Originality/value**—This study is among the first attempts to streamline the theoretical
23 discourses relating to BBB for IM in a construction context. It contributes to the construction
24 IM by directing attention to key IM requirements and processes rooted in the IM literature.

25 **Keywords:** building information modeling; information management; information quantity;
26 information quality; information accessibility

27

28 **1. Introduction**

29 Construction project and asset management (CPAM) generally involves multi-disciplinary
30 professionals working together to construct and manage a given asset. Against this backdrop,
31 the critical role of information management (IM) to overall CPAM performance cannot be
32 overemphasized. CPAM in essence is an array of decisions made by different participants
33 across the lifecycle of an asset based on the available information (Flanagan and Lu, 2008).
34 Given the complex nature of CPAM nowadays, these decisions are more closely interrelated.
35 This implies the reality of even greater uncertainty caused by increasingly dynamic information
36 on which decision-making is dependent. The management of information, in layman's terms,
37 is the making of accurate information available at the right time in the right format to the right
38 person (Chen et al., 2015). The fundamental goal of IM is to support efficient and effective
39 decisions by harnessing the value of information (Choo, 2002). In this way, IM is key to
40 managing changes, informing decisions, and maintaining the integrity of an asset's functional
41 and physical attributes to meet the demands of the owners, users, etc., i.e., to establish the
42 configuration of a CPAM approach that is tuned to the project at hand (Love et al., 2014; Tezel
43 and Aziz, 2017).

44 The importance of IM coupled with the rapid advancement of information technologies has
45 directed the attention of CPAM towards building information modeling (BIM) (Eastman et al.,
46 2011). As the digital representation of physical and functional characteristics of a facility, BIM
47 is widely accepted to be an effective tool to store, integrate, and share dynamic information
48 from different stages of an asset's planning, construction, and occupation to facilitate
49 communication and the use of information (Eastman et al., 2011; Love et al., 2014; Xu et al.,
50 2014).

51 The potential benefits of BIM in supporting IM have been broadly discussed in the ample set
52 of literature (e.g., Demian and Walters, 2014; Hoeber and Alsem, 2016; Beach et al., 2017). In
53 understanding the potentials of BIM, many researchers acknowledge the existing obstacle of
54 bringing BIM into play in practices, which raises immediate questions about how to make
55 effective use of BIM for IM in real-life construction projects (e.g., Xu et al., 2014; Chen et al.,
56 2015; Edirisinghe et al., 2017). Notably, Chen et al. (2015) have partly answered this question
57 by developing a conceptual framework of 'Bridging BIM and Building (BBB)'. The BBB
58 conceptual framework highlights the importance of information synchronization between BIM
59 and actual CPAM processes, which echoes the concepts of a Cyber-Physical System (CPS)
60 (Anumba et al., 2010) and a digital twin (Tao et al., 2017) in a broader sense. Chen et al. (2015)
61 further argued that the potentials of BIM are more likely to be achieved if utilizing BIM in a
62 way towards BBB, i.e., continually updating a BIM model with accurate, reliable project
63 information and supporting the timely sharing of information.

64 Several researchers have recognized Chen et al.'s (2015) conceptual framework of BBB (e.g.,
65 Ghaffarianhoseini et al., 2017; Sun et al., 2017). Nevertheless, at least three questions remain
66 unaddressed in the existing literature. First, the underlying mechanism, or figuratively, the
67 'epistemological link', through which BBB could support IM remains unclear. Second, issues

68 about how to develop possible system architectures of the BBB conceptual framework have
69 yet to be fully addressed. Finally, with some notable exceptions, very few studies have
70 empirically examined the contribution of BBB to IM in construction.

71 This paper draws upon the BBB conceptual framework and the IM literature to make three
72 contributions. First, it demystifies the underlying mechanism of how BBB could contribute to
73 IM. Three IM requirements, namely, requirements on information quantity, quality, and
74 accessibility are identified as significant mediators between BBB and IM. Second, it introduces
75 the system architecture and the deployment procedures of BBB. Third, it illuminates the
76 implementation of a BBB system in a real-life prefabricated construction project. Based on this
77 project, a case study has been done to empirically test the demystified ‘epistemological link’
78 between BBB and IM.

79 The following section reviews the relevant literature, covering explanations of IM in CPAM
80 and the role of BIM for IM. In Section 3, the authors proceed to discuss the mechanism linking
81 BBB and IM by identifying significant IM requirements. In Section 4, a system architecture of
82 BBB and its operational procedures are provided. A case study is presented in Section 5, and
83 the evaluation results about how BBB can improve IM are provided in Section 6. Conclusions
84 are drawn in the final segment of the paper.

85

86 **2. Literature review**

87 ***2.1 IM in CPAM***

88 For all types of organizations, IM is critically relied upon to harness the value of information
89 for environmental adaptation and internal coordination (Choo, 2002). IM is an umbrella term
90 for activities associated with organizational participants’ information-related behaviors and
91 how they help achieve their strategic purposes (Choo, 2002). The primary elements of IM

92 procedures include the development of information systems for and policies around the work
93 of information acquisition, storage, retrieval, processing, interpretation, communication, and
94 use (Maes, 2007).

95 Given the complexity of CPAM, the literature commonly agrees that IM strategically benefits
96 decision-making and problem-solving across a project's lifecycle (e.g., Chassiakos, 2007; Xu
97 et al., 2014). A construction project can be viewed as a process of aligning numerous separate
98 resources upon a particular location over a reasonable amount of time and sequence, at bearable
99 prices, and with desired quality (Sawhney et al., 1998). In order to be well managed, it requires
100 superiorly performed coordination and sets a high standard for the elimination and handling of
101 uncertainty and interdependence between activities (Dubois and Gadde, 2002). Uncertainty in
102 construction could be caused by those unpredictable and uncontrollable factors existing in both
103 the internal and external environments of an asset. While all businesses confront
104 unpredictability and uncontrollability, the construction industry is especially vulnerable to such
105 factors due to its heterogeneous production process (Dubois and Gadde, 2002).

106 Another determinant of CPAM complexity—interdependence—arises from the close
107 interrelationships between decisions made at all stages of an asset (Lu and Olofsson, 2014).
108 For example, for construction and facility management activities, various personnel need
109 decisions made by designers, e.g., the design drawings, to support their decision-making and
110 ongoing work (Nourbakhsh et al., 2012). A trivial change in one design decision may produce
111 a domino effect, altering activities throughout the construction and operation stages (Love et
112 al., 2014). As such, uncertainties present in the miscellaneous activities and interdependencies
113 between participants throughout an asset's lifecycle pose real challenges to realizing CPAM
114 configuration. Thus, an adequate amount of high quality, accessible information is needed for
115 making decisions as rationally as possible (Amendola, 2002). Hence, IM is essential to CPAM

116 by solving information problems arising from uncertainty and interdependency that
117 participants and their activities often circumvent (Martínez-Rojas et al., 2015).

118

119 ***2.2 Prior research on BIM for IM***

120 Since its introduction three decades ago, BIM has rapidly developed. This cutting-edge
121 information technology management system has been applied to CPAM in most global
122 construction industries (Eastman et al., 2011). BIM enables novel ways for project stakeholders
123 to illustrate design, construction, and operations details, as well as more effective exchange and
124 use of information, thereby developing a more agile and in-depth understanding of the
125 configuration of CPAM (e.g., Xu et al., 2014; Love et al., 2014). As Love et al. (2014) argued,
126 the benefits of BIM are realized most when it allows different stakeholders to perform their
127 roles more efficiently and effectively.

128 Prior studies have exposed BIM's various capabilities for supporting IM (e.g., Love et al., 2014;
129 Hoerber and Alsem, 2016; Beach et al., 2017). In understanding the benefits of BIM, many
130 studies focused on conceptualizations and expressed the potentials of BIM in future scenarios
131 as "idealistic goals" (Miettinen and Paavola, 2014). However, many researchers suggest the
132 conceptualization of BIM's potentials cannot validate its effectiveness (e.g., Barlish and
133 Sullivan, 2012; Zheng et al., 2017). According to them, BIM continuously effects the ways
134 participants do their work. Thus, the evaluations on BIM should consider the entire process of
135 associated operations instead of solely focusing on the final results. Furthermore, from the
136 empirical perspective, very few studies have empirically assessed the significance of BIM to
137 IM in construction. The existing empirical BIM studies, nonetheless, fail to offer a systematic,
138 detailed link between BIM and its advantages in supporting IM.

139

140 **2.3 Recapitalizing the conceptual framework of BBB**

141 A potential reason to the above-specified deficiencies in both the theoretical and empirical BIM
142 literature is the fact that using BIM alone cannot provide a permanent IM platform for
143 alleviating the problems caused by the temporary nature and heterogeneity (e.g., uniqueness,
144 fragmentation, and discontinuity) of construction projects. As Chen et al. (2015) argued, an
145 architectural or structural BIM model would remain static if the information it contains cannot
146 be synchronized with dynamic project processes. Thus it risks being ‘blind and deaf’, failing
147 to go very far in supporting IM in construction. An ‘as-built’ BIM model that reflects the
148 ongoing CPAM process, comparatively, is proposed to be more reliable and effective in
149 supporting IM across an asset lifecycle. Against this proposition, Chen et al. (2015) developed
150 the conceptual framework of BBB to take full advantage of BIM.

151 Chen et al. (2015) defined BBB as “connecting the information contained in BIM with physical
152 building processes to make BIM reflecting real-life situations”. The BBB conceptual
153 framework consists of the building layer, intermediate layer, and BIM layer (see Figure 7 in
154 Chen et al. [2015]). The building layer involves activities in a project, of which various types
155 of information are collected and processed. The intermediate layer organizes information
156 storage and interoperability. The BIM layer refers to the BIM model, which presents the real-
157 life project situation for decision support. According to the principle of the BBB conceptual
158 framework, as the project progresses, the BIM model should be updated continuously with
159 information passing through the intermediate layer and integrating with BIM objects
160 accordingly. Considering the linkage between BIM’s potentials and the BBB conceptual
161 framework, this paper shows its importance in providing a conceptualized way for empirical
162 evaluations on impacts of BIM through demystifying the mechanism through which BBB
163 contributes to IM.

164

165 **3. Mechanism linking BBB and IM**

166 BBB underlines the management of information rather than technology. Accordingly, an
167 operable system developed following the BBB conceptual framework (thereafter named a BBB
168 system) should allow the collection, storage, process, and communication of various types of
169 project information, providing seamless connectivity between BIM and the physical project
170 process. A BBB system influences the satisfaction of three IM requirements, namely,
171 information of adequate quantity, high quality, and easy accessibility. These requirements in
172 turn are important antecedents for desired IM performance. Thus, the authors posit that these
173 three IM requirements mediate the links between BBB and IM in construction.

174 *Information quantity*

175 This requirement defines the need for a sufficient amount of information in order to cope with
176 uncertainty. As argued by Galbraith (1973), the more diverse the goals, the more variable the
177 tasks, and the more significant the interdependencies, the more information necessary to reduce
178 uncertainty. Construction projects need more than just a variety of information on
179 interdependent tasks, resources, technologies, etc. Information emerges continuously whenever
180 a task completes or a new task is issued. When only limited information is available, serious
181 problems like project delays and budget overrun can ensue (Eastman et al., 2011). Thus, IM in
182 construction should ensure the collection and processing of a sufficient amount of information
183 in a timely and continuous manner.

184 A BBB system can significantly enable the provision of a sufficient amount of information.
185 Hajian and Becerik-Gerber (2009) explained that the use of BIM together with data-acquisition
186 technologies allows comprehensive project information to become available. This is
187 understood by connecting users' information needs and BIM's definition. In construction

188 projects, managers and workers' information needs essentially relate to building components.
189 Information from each component relates to an entity, e.g., material and labor, centered on a
190 component. In a BIM model, a digital object represents a building component. The
191 implementation of BBB allows a BIM object to timely reflect all information related to its
192 corresponding physical component (Eastman et al., 2011). In so doing BIM can provide the
193 comprehensive information that encompasses design documents, construction progresses,
194 stakeholders, resources, activities, changing relationships, etc. Thus, the authors assert that the
195 implementation of a BBB system meets the IM requirement of information quantity.

196 ***Information quality***

197 This requirement defines the need of quality information to handle equivocality and quickly
198 specify the required information. In construction projects, managers often need to translate
199 events into information, and then transmit, communicate, and transform it into decisions. Great
200 equivocality might emerge during this process, causing difficulties in communication and
201 decision-making (Weick, 1979). It is also worth noting that, when seeking to satisfy the
202 requirement on information quantity, an additional piece of information may also trigger
203 divergence and ambiguousness, thus increasing equivocality (Espejo and Watt, 1988).
204 Furthermore, when information is overwhelmed, users find it hard to identify the information
205 they need promptly, which in turn hinders their decisions (Choo, 2002). Thus, a well performed
206 IM involves more than processing the amount of information; information quality is also a core
207 concern (Daft and Weick, 1984).

208 A BBB system is a significant enabler of the provision of quality information. First, by
209 minimizing the manual work in the collection and processing of information, BBB eliminates
210 the difference between information in BIM and the physical construction and avoids losses of
211 information (Chen et al., 2015). The *timeliness* and *accuracy* of information can thus be

212 ensured. Furthermore, through the 3D visualization of information, BBB provides the
213 information of *conciseness* as suggested by organizational researchers (e.g., Daft and Lengel,
214 1986). Finally, a BBB system enables the intelligent retrieval and fast, responsive presentation
215 of information in response to users' information needs, ensuring the *relevance* of information.
216 The highlighted information attributes, i.e., *timeliness*, *accuracy*, *conciseness*, and *relevance*,
217 most often appear in information researchers' constructs of information quality (e.g., Wand and
218 Wang, 1996). Thus, the authors propose the implementation of a BBB system meets the IM
219 requirement of information quality.

220 ***Information accessibility***

221 This requirement defines the need for accessible information to allow efficient and effective
222 decision-making. In construction projects, management information boasts a fairly wide variety,
223 often from disparate sources and not easily accessible when traditional IM approaches are being
224 used (Goedert and Meadati, 2008). Ideally, managers and workers should acquire information
225 from sources that offer quality information. However, information users are found to be
226 inclined toward using sources shown to provide "the most conveniently accessible"
227 information regardless of the quality of that information (Fidel and Green, 2004). Such
228 behavior can massively impede appropriate decision-making. Thus, an effective IM approach
229 needs to make the quality information easily accessible to information users.

230 A BBB system is a significant enabler of the provision of accessible information as it allows
231 different users to reach information in BIM through a range of mobile terminals, e.g., personal
232 computers, tablets. In so doing, a BBB system qualifies as an application of a web-based
233 management information system (MIS). Lam and Chang (2002) find that project stakeholders
234 can overall check project information without time and location limitations if a web-based MIS
235 is being used. Chassiakos and Sakellariopoulos (2008) also emphasize the contribution of web-

236 based MIS to the interoperability and exchange of information in construction projects. Thus,
237 the authors propose that the implementation of a BBB system meets the IM requirement of
238 information accessibility.

239

240 **4. BBB system development**

241 ***4.1 System architecture***

242 In this study, a feasible BBB system is developed based on proper technologies and efforts
243 directed to satisfy the three IM requirements discussed above. The system architecture contains
244 four components, i.e., an *information collection component*, *gateway*, *database*, and *cloud-*
245 *based BIM platform* (see Figure 1). Between each two components, communication networks
246 are developed to provide channels for bidirectional information transfer and communication.
247 Many types of wired or wireless communication networks exist, including Zigbee and
248 Bluetooth, Wide Area Networks (WAN), and Local Area Networks (LAN). The selection of
249 networks should consider factors, such as cost, distance, and requirements on speed contingent
250 to a particular project. A brief introduction of the four components is presented as follows.

- 251 I. The *information collection component* consists of different devices, e.g., laser scanner,
252 Auto-ID, sensors, for sensing both geometric and non-geometric information. The
253 selection of proper devices could be based on the type of required information.
- 254 II. The *gateway* provides four essential functions for different formats of information
255 transferring from the physical project to BIM and vice versa. These functions include
256 the configuration of information-acquisition devices, information filtering and pre-
257 processing, temporary storage of information, and manual input of information when
258 necessary. This component can be developed by installing tailor-programmed gateway

259 software in either stationary workstations or hand-held devices, e.g., a smartphone.

260 III. The *database* is used to store the collected information passing through the gateway
261 and the as-design information retrieved from BIM, which includes but is not limited to
262 the geometry, orientation, and specification of BIM components. The information is
263 stored in different types, like numeric or string types, and can be requested by using the
264 Structured Query Language (SQL).

265 IV. The *cloud-based BIM platform* processes and visualizes the information and enables
266 information exchange and sharing between stakeholders. This component is developed
267 by transferring the information contained in BIM into required formats, storing the
268 transferred information in the database, using Application Protocol Interface (API) to
269 render interactive 3D graphics, e.g., Web Graphics Library (WebGL), to reconstruct the
270 BIM model in a cloud server, and then programming function modules in BIM to permit
271 the processing of information. The BIM platform is thus cloud-based, which supports
272 remote access to BIM models and services online through a variety of devices. Using
273 protocols such as HTTP and FTP, interfaces between the cloud-based BIM platform and
274 the database are developed to enable the platform to actively request or passively
275 receive data from the database.

276 <Please insert Figure 1 here>

277

278 ***4.2 Deployment procedures***

279 Four-step deployment procedures are provided to further the system architecture of BBB (see
280 Figure 2). First concerns determining the project management tasks, e.g., schedule control and
281 quality management, needing certain types of information to be managed by BBB. Although
282 BBB ideally can manage all geometric and non-geometric project information, the more types

283 of information to be managed indicate higher cost and requirements on technology, personnel,
284 etc. Next is identifying the types and sources of the required information. The third step is to
285 develop the four BBB components, i.e., information-acquisition technologies, gateway(s),
286 database(s), cloud-based BIM platform(s), by using proper hardware and software technologies.
287 The last step is to integrate all BBB components to form a BBB system that is operable and
288 feasible for managing the required information in the construction project.

289 <Please insert Figure 2 here>

290

291 **5. Case study**

292 This section illuminates the implementation process of the BBB system in actual situations.
293 The case is a real-life prefabricated construction project in Hong Kong. One building block of
294 the project was selected to apply the BBB system. The building block has thirty-eight floors
295 and needs 7,103 pieces of prefabricated components of thirteen different types, e.g., façade,
296 slab, and bathroom. All prefabricated components are produced in an offshore prefabrication
297 factory (Company A) in Guangdong, China. The transportation services are provided by a third-
298 party logistics company (Company B). The main contractor (Company C) is a leading local
299 Hong Kong contractor. In this case study, the authors performed two roles: (1) consultants for
300 providing a BBB system to the managers and workers of the three companies; and (2) observers
301 on the BBB system implementation without any intervention on managers and workers' daily
302 operations.

303

304 ***5.1 Development of the BBB system***

305 As shown in Figure 2, the first two steps of the deployment procedures of BBB is determining

306 the target information necessary for managing and identifying the types and sources of the
307 target information. The authors visited the construction site and the prefabrication factory every
308 other week to observe the existing workflow (see Figure 3) for two months, totalling eight site
309 visits, i.e., four to the prefabrication factory and four to the construction site. By doing so three
310 significant IM problems embedded in the processes of prefabrication production, transportation,
311 and on-site assembly were identified. First, the paper-based IM methods used during the project
312 often caused issues around duplicated information input and loss of information. Second,
313 existing IM methods were not interoperable, preventing managers from the three companies
314 from perceiving a full picture as the project progressed. Third, delayed communication
315 frequently occurred between the three companies, even sometimes within a single company.
316 Consequently, managers and workers seldom had timely information for decisions and
317 guidance for action-taking. Thus, management and operation mistakes were unavoidable and
318 the on-site working processes were often interrupted.

319 <Please insert Figure 3 here>

320

321 The identified problems were confirmed by managers and workers from the three companies
322 through a focus meeting. The meeting participants generally expressed that the information
323 visibility and traceability of prefabricated components should have been more effectively
324 managed to ensure a smooth project delivery. Hence, the required information was identified
325 to be the information about prefabricated components, i.e., quality, status, and location of each
326 prefabricated component, as well as responsible persons and other resources during the
327 offshore production, cross-border transportation, and on-site assembly.

328 Based on the types and sources of the target information requiring management, the authors
329 compared several technologies (see Figure 1) to select the proper hardware and software for

330 developing a BBB system. The hardware included radio frequency identification (RFID)
331 devices, smartphones, and computers. Two types of RFID tags were used, ultra-high frequency
332 (UHF) tags attached to the reinforcement cage of each prefabricated component and high
333 frequency (HF) tags attached to machinery, e.g., trucks, trailers. Two types of RFID reader
334 were also used, UHF RFID Reader to read UHF tags and Near Field Communication (NFC)
335 module embedded in the smartphone to read HF tags. The smartphone was also used as the
336 mobile gateway. A tailor-made gateway app was installed on the smartphone for two purposes:
337 (1) to configure all tag-attached components for administrating the information collection; and
338 (2) to record additional information by manual input. Computers connected to the Internet were
339 used by the managers to access the web services of the BBB system.

340 The software of the BBB system was primarily associated with the development of three cloud-
341 based BIM platforms, including the prefabricated production platform (PPP), the prefabricated
342 transportation platform (PTP), and the on-site assembly platform (OAP). Each platform
343 consisted of a smartphone app developed for workers and a web service developed for
344 managers. The OAP database stored the design information of each prefabricated component
345 and the on-site assembly information. PPP and PTP databases stored information on the
346 production and transportation processes, respectively. The three platforms shared one BIM
347 model, which was developed in four steps: (1) develop the BIM model in Autodesk Revit, in
348 which each BIM object, e.g., wall, door, column, has complete design information and a unique
349 name for identification (Chen et al., 2017); (2) organize and import the information of all BIM
350 objects into the database of OAP; (3) generate JavaScript Object Notation (JSON) files by
351 compiling information on BIM objects; and (4) interpret the JSON files by WebGL to show the
352 BIM model on the web services.

353

354 **5.2 System implementation**

355 The authors first provided four training sessions to the selected managers and workers of the
356 three companies before they began to use the BBB system in their daily work. At the time of
357 system implementation, the construction of the first thirteen floors, i.e., G/F-12/F, of the project
358 had been completed. Therefore, the BBB system was used in the construction of the remaining
359 twenty-five floors, i.e., 13/F-37/F, which had 5,070 prefabricated components. The system was
360 implemented for eleven months from July 2015 to May 2016, after which, the case project was
361 completed. The following reports the actual implementation of the BBB system in the
362 production, transportation, and on-site assembly processes based on the authors' monthly site
363 visits during the eleven-month period of system implementation.

364 **Production**—To start, the project manager of Company C selected the type of prefabricated
365 components in the web service of OAP and set the date when these components should be
366 delivered to the construction site. OAP automatically generated an order containing all
367 information of required components, e.g., type, component code, and quantity, and sent the
368 order to the PPP. After receiving the order, the manager of Company A established the
369 production plan in the web service of the PPP and set the planned production date of each
370 component. Workers would receive the daily production plan via the smartphone app. During
371 the production, the worker attached a UHF tag to the reinforcement cage of a prefabricated
372 component and scanned the tag to record the production information using the smartphone app.
373 The smartphone app then uploaded the recorded information to the PPP database. In addition,
374 OAP would automatically receive the information on the prefabricated components from PPP
375 and present the information in the BIM model.

376 **Transportation**—The process started with a delivery order made by the manager of Company
377 C in the web service of OAP. The delivery order was then automatically sent to PPP, in which

378 the manager of Company A established the transportation plan and arranged the loading tasks.
379 Workers of Company A would find the required prefabricated component by scanning its RFID
380 tag. Once confirmed, the component was loaded onto the trailer. The worker linked the loaded
381 component with the trailer by selecting the component code in his smartphone app and
382 scanning the RFID tag of the trailer with the smartphone. In the web service of PTP, the
383 manager of Company B checked the availability of drivers and trucks and assigned
384 transportation tasks. The driver of Company B used the smartphone app to check the
385 transportation task. Before departure, the driver scanned the RFID tag of the truck with the
386 smartphone to confirm it as the correct truck, and also scanned the tag of the trailer for
387 confirmation. On the way from the storage yard towards the construction site, the driver
388 updated the transportation information in the smartphone app when passing the cross-border
389 customs and approaching the construction site. The updated transportation information would
390 be stored in the PTP database and shared with OAP to be shown in the BIM model.

391 ***On-site assembly***—Based on the information on prefabricated components from PPP and PTP,
392 the project manager of Company C formulated the on-site assembly plan, which included
393 allocating labor forces and dispatching machines, in the web service of OAP. Then, workers
394 reviewed their tasks through the smartphone OAP app. After the component was lifted onto the
395 floor, the erection operator scanned the RFID tag to collect its position information by using
396 the GPS sensor of the smartphone. In case the difference between the actual position and the
397 as-designed position exceeded the tolerance, i.e., the component was placed wrongly,
398 corrections would be made immediately before the prefabricated component was connected
399 with the in-situ concreting structure. After that, a quality controller scanned the tag of the
400 installed prefabricated component to record the quality information in the smartphone app. All
401 collected information during the on-site assembly was timely recorded in the database of the

402 OAP and presented in the BIM model of the web service. The project manager would review
403 the current progress and inventory for placing the next round of order.

404

405 **6. Evaluating the epistemological link between BBB and IM**

406 *6.1 Data collection and analytical methods*

407 In this case study, two types of data were collected for evaluation. The first type of data was
408 about the participants' task operations before and after the implementation of the BBB system.
409 As introduced in Table 1, the operation data before the system implementation were collected
410 through archived project documents and the authors' observation at the prefabrication factory
411 and the construction site. The operation data after the system implementation were recorded by
412 the BBB system and obtained from the authors' observations. The second type of data was the
413 end-users' feedback collected from ten semi-structured interviews. The interviews were
414 conducted at interviewees' offices, each of which took about thirty minutes. The interviewees
415 comprised two workers and one manager from Company A, two drivers and one manager from
416 Company B, and two workers and two managers from Company C (see Table 2). All
417 interviewees were end-users of the BBB system.

418 <Please insert Table 1 here>

419

420 <Please insert Table 2 here>

421

422 For analytical purposes, data of the project participants' task operations before and after the
423 system implementation were compared in order to determine whether their working
424 efficiencies were improved or not. The analysis of the second type of data was to interpret how

425 BBB could impact the performance of IM in this case. The method of phenomenological
426 analysis was adopted since it helps to identify key factors that make given phenomena or
427 experience distinguishable from others and to find out how people are perceiving specific
428 situations they are facing (Pietkiewicz and Smith, 2014).

429

430 **6.2 Evaluation results**

431 By analyzing the data from the interviews, Table 3 summarizes important interviewee feedback.
432 Explicitly, results associated with impacts of BBB on IM include: (1) providing all information
433 needed for tasks at hand (80% agreed); (2) enabling timely information collection and exchange
434 (100% agreed); (3) providing accurate information for planning and control (90% agreed); (4)
435 allowing end-users to review relevant information through simple operations (90% agreed); (5)
436 presenting the information in a concise way without any redundancy (80% agreed); and (6)
437 assisting remotely track and review the project information (90% agreed). Overall, the
438 feedback showed that the BBB system helped improve information quantity, quality, and
439 accessibility, the requirements of IM, in the case project and participants were satisfied.

440

<Please insert Table 3 here>

441

442 Inquiry into the on-site observation and the recorded operation data revealed the effectiveness
443 of the BBB system implementation in accomplishing the determined project management task,
444 i.e., tracking and monitoring the prefabricated components during off-site production,
445 transportation, and on-site assembly processes. During the prefabrication process, several
446 significant improvements after the use of the BBB system were noted: (1) since both the
447 production orders from Company C and the production tasks made by Company A were in a
448 digital format, the paperwork for information recording was greatly reduced from 250 sheets

449 per day to 125 sheets per day; (2) the efficiency of Company A's reactions to Company C's
450 design and order changes was much higher than before, which successfully reduced the
451 production cycle from ten days to six; (3) the average "working-in-process inventory" was
452 decreased from 110 sets to 98 sets as the manager of Company A made production plans more
453 accurate; and (4) the average time spent locating a prefabricated component for transport
454 decreased from 7-8 minutes to 5-6 minutes, which may be trivial for a single component, but
455 becomes significant considering the sizeable number of total components produced on a single
456 project.

457 During the transportation process, three key improvements in the process efficiency were made
458 with the aid of the BBB system. First, the average time needed for a driver to receive his/her
459 task and fetch the truck, i.e., "time for order picking", was reduced from 2 to 1.2 hours. The
460 main benefit of this concerned the manager of Company B being able to timely check the most
461 up-to-date transportation plans and plan transportation tasks accurately based on the automatic
462 prioritization of tasks enabled by the web-based BBB system. Second, the average "waiting
463 time for delivery" was reduced from 2 to 1.5 hours, and no delivery error was observed during
464 the entire length of BBB system implementation. Third, the paper documents decreased from
465 five sheets per car to three sheets because delivery dockets became simpler owing to escaping
466 duplicated entry of information.

467 During the on-site assembly process, two important improvements in process efficiency were
468 brought by the BBB system implementation. Firstly, the synchronization of information
469 contained in the three platforms saved time considerably and reduced the use of resources for
470 daily operation compared to the conventional paper-based method. The BBB system helped
471 the manager of Company C review the real-time locations of prefabricated components, which
472 contributed to site management by determining more accurate on-site buffers to maintain the

473 construction progress. With the help of the BBB system, the time that workers spent on
474 recording the installation of a single wing of twenty-three facades was reduced by fourteen
475 minutes compared to the paper-based method, and the time required for locating a needed
476 component decreased from six minutes to three minutes. Secondly, the manager of Company
477 C reported that three prefabricated components were found to be assembled at the wrong
478 location before the implementation of the BBB system. In contrast, the BBB system confirmed
479 and verified key on-site assembly steps, and no wrong on-site assembly was observed during
480 the system implementation. The accuracy rate of on-site assembly thus increased from 99.85%
481 (i.e., 2030 out of 2033) to 100%, which saved considerable reproduction and reinstallation
482 costs.

483

484 **7. Conclusion**

485 Over the years, the rapid development of BIM has successfully mainstreamed the system into
486 IM in almost every aspect of the construction project. The conceptual framework of BBB is
487 amongst the first attempts to make BIM more useful for IM by advocating the communication
488 of stakeholders and delineating different technologies and their associated software, database,
489 and information exchange protocols (Chen et al., 2015). This paper furthered the understanding
490 of the BBB conceptual framework and demystified the mechanism through which BBB can
491 truly impact IM. It did so by developing an operable system architecture of BBB and
492 implementing a BBB system in a prefabricated construction project in Hong Kong. A two-year,
493 participatory case study based on this actual project corroborated that BBB can improve IM in
494 construction.

495 Of particular interest is the research's attempt to understand the mechanism linking BBB and

496 IM. This study proposed that the information quantity, quality, and accessibility are significant
497 mediators between BBB and IM in construction, and the case study supported this proposition.
498 Practitioners can pay extra attention to these three aspects in designing their own BBB systems,
499 with a view to making BIM a truly useful decision-supporting tool. It is worth noting that the
500 information quantity, quality, and accessibility identified in this study are by no means the
501 entire aspects for understanding the mechanism through which BBB can impact IM, but they
502 provide directions to crack challenging IM problems in construction projects.

503 This study contributes to the construction IM literature by directing attention to key IM
504 requirements and processes rooted in the IM literature. It is also of practical significance by
505 providing a system architecture for BBB, its deployment procedures, and good practices that
506 bridge BIM and building for better IM in a construction project context. Although the BBB
507 system and the deployment procedures are illustrated in a prefabricated construction project
508 context, they can be readily transplanted to other projects types, e.g., cast in-situ technologies.

509 The components and their linkage developed in the BBB system architecture are generally
510 applicable to typical scenarios of CPAM throughout a project lifecycle. Future research is
511 suggested to (1) apply the conceptual framework of BBB and develop BBB systems for IM at
512 the operation stage or the configuration management across an asset's lifecycle, and (2)
513 develop more types of BBB systems to manage other types of project information, such as the
514 real-time location of workers and the project cash flow in both cast in-situ and prefabricated
515 construction projects.

516

517 **Acknowledgement**

518 The authors would like to acknowledge the financial support of the General Research Fund

519 (GRF) (Grant No.: 17205614) by Hong Kong Research Grant Council (RGC) and the
520 Innovation and Technology Fund (Grant No.: ITP/045/13LP) by the Hong Kong Innovation
521 and Technology Commission (ITC). The authors would also like to thank the Hong Kong
522 Housing Authority and the three companies for conducting the two-year case study.

523

524 **References**

525 Amendola, A. (2002). Recent paradigms for risk informed decision making. *Safety*
526 *Science*, 40(1-4), 17-30.

527 Anumba, C. J., Akanmu, A., and Messner, J. (2010). Towards a cyber-physical systems
528 approach to construction. In *Construction Research Congress 2010: Innovation for*
529 *Reshaping Construction Practice* (pp. 528-537).

530 Barlish, K., and Sullivan, K. (2012). How to measure the benefits of BIM—A case study
531 approach. *Automation in Construction*, 24, 149-159.

532 Beach, T., Petri, I., Rezgui, Y., and Rana, O. (2017). Management of collaborative BIM data
533 by federating distributed BIM models. *Journal of Computing in Civil Engineering*, 31(4),
534 04017009.

535 Chassiakos, A. P., and Sakellariopoulos, S. P. (2008). A web-based system for managing
536 construction information. *Advances in Engineering Software*, 39(11), 865-876.

537 Chen, K., Lu, W., Peng, Y., Rowlinson, S., and Huang, G. Q. (2015). Bridging BIM and
538 building: From a literature review to an integrated conceptual framework. *International*
539 *Journal of Project Management*, 33(6), 1405-1416.

540 Chen, K., Lu, W., Wang, H., Niu, Y., and Huang, G. G. (2017). Naming objects in BIM: A
541 convention and a semiautomatic approach. *Journal of Construction Engineering and*

542 Management, 143(7), 06017001.

543 Choo, C. W. (2002). Information management for the intelligent organization: The art of
544 scanning the environment. Information Today, Inc.

545 Daft, R. L., and Lengel, R. H. (1986). Organizational information requirements, media richness
546 and structural design. *Management Science*, 32(5), 554-571.

547 Daft, R. L., and Weick, K. E. (1984). Toward a model of organizations as interpretation systems.
548 *Academy of Management Review*, 9(2), 284-295.

549 Demian, P., and Walters, D. (2014). The advantages of information management through
550 building information modelling. *Construction Management and Economics*, 32(12),
551 1153-1165.

552 Dubois, A., and Gadde, L. E. (2002). The construction industry as a loosely coupled system:
553 implications for productivity and innovation. *Construction Management and Economics*,
554 20(7), 621-631.

555 Eastman, C., Teicholz, P., Sacks, R., and Liston, K. (2011). *BIM handbook: A guide to building*
556 *information modeling for owners, managers, designers, engineers and contractors*. John
557 Wiley & Sons.

558 Edirisinghe, R., London, K. A., Kalutara, P., and Aranda-Mena, G. (2017). Building
559 information modelling for facility management: are we there yet?. *Engineering,*
560 *Construction and Architectural Management*, 24(6), 1119-1154.

561 Espejo, R., and Watt, J. (1988). Information management, organization and managerial
562 effectiveness. *Journal of the Operational Research Society*, 39(1), 7-14.

563 Fidel, R., and Green, M. (2004). The many faces of accessibility: Engineers' perception of
564 information sources. *Information Processing & Management*, 40(3), 563-581.

565 Flanagan, R., and Lu, W. (2008). Making informed decisions in product-service systems. In

566 IMechE Conference, Knowledge and Information Management Through-Life. Institute
567 of Mechanical Engineers, London.

568 Galbraith, J. R. (1973). Designing complex organizations. Addison-Wesley Longman
569 Publishing Co., Inc.

570 Ghaffarianhoseini, A., Tookey, J., Ghaffarianhoseini, A., Naismith, N., Azhar, S., Efimova, O.,
571 and Raahemifar, K. (2017). Building Information Modelling (BIM) uptake: Clear
572 benefits, understanding its implementation, risks and challenges. Renewable and
573 Sustainable Energy Reviews, 75, 1046-1053.

574 Goedert, J. D., and Meadati, P. (2008). Integrating construction process documentation into
575 building information modeling. Journal of Construction Engineering and
576 Management, 134(7), 509-516.

577 Hajian, H., and Becerik-Gerber, B. (2009). A research outlook for real-time project information
578 management by integrating advanced field data acquisition systems and building
579 information modeling. In Computing in Civil Engineering (2009) (pp. 83-94).

580 Hoerber, H., and Alsem, D. (2016). Life-cycle information management using open-standard
581 BIM. Engineering, Construction and Architectural Management, 23(6), 696-708.

582 Lam, H. F., and Chang, T. Y. P. (2002). Web - based information management system for
583 construction projects. Computer-Aided Civil and Infrastructure Engineering, 17(4), 280-
584 293.

585 Love, P. E., Matthews, J., Simpson, I., Hill, A., and Olatunji, O. A. (2014). A benefits realization
586 management building information modeling framework for asset owners. Automation in
587 Construction, 37, 1-10.

588 Lu, W., and Olofsson, T. (2014). Building information modeling and discrete event simulation:

589 Towards an integrated framework. *Automation in Construction*, 44, 73-83.

590 Maes, R. (2007). An integrative perspective on information management. *Information*
591 *Management: Setting the Scene*, 11-26.

592 Martínez-Rojas, M., Marín, N., and Vila, M. A. (2015). The role of information technologies
593 to address data handling in construction project management. *Journal of Computing in*
594 *Civil Engineering*, 30(4), 04015064.

595 Miettinen, R., and Paavola, S. (2014). Beyond the BIM utopia: Approaches to the development
596 and implementation of building information modeling. *Automation in Construction*, 43,
597 84-91.

598 Nourbakhsh, M., Mohamad Zin, R., Irizarry, J., Zolfagharian, S., and Gheisari, M. (2012).
599 Mobile application prototype for on-site information management in construction
600 industry. *Engineering, Construction and Architectural Management*, 19(5), 474-494.

601 Pietkiewicz, I., and Smith, J. A. (2014). A practical guide to using interpretative
602 phenomenological analysis in qualitative research psychology. *Psychological Journal*,
603 20(1), 7-14.

604 Sawhney, A., AbouRizk, S. M., and Halpin, D. W. (1998). Construction project simulation
605 using CYCLONE. *Canadian Journal of Civil Engineering*, 25(1), 16-25.

606 Sun, C., Jiang, S., Skibniewski, M. J., Man, Q., and Shen, L. (2017). A literature review of the
607 factors limiting the application of BIM in the construction industry. *Technological and*
608 *Economic Development of Economy*, 23(5), 764-779

609 Tao, F., Cheng, J., Qi, Q., Zhang, M., Zhang, H., and Sui, F. (2018). Digital twin-driven product
610 design, manufacturing and service with big data. *The International Journal of Advanced*
611 *Manufacturing Technology*, 94(9-12), 3563-3576.

612 Tezel, A., and Aziz, Z. (2017). Visual management in highways construction and maintenance

613 in England. *Engineering, Construction and Architectural Management*, 24(3), 486-513.

614 Wand, Y., and Wang, R. Y. (1996). Anchoring data quality dimensions in ontological
615 foundations. *Communications of the ACM*, 39(11), 86-95.


616 Weick, K. E. (1979). *The social psychology of organizing*. Reading, Mass. Addison-Wesley.

617 Xu, X., Ma, L., and Ding, L. (2014). A framework for BIM-enabled life-cycle information
618 management of construction project. *International Journal of Advanced Robotic Systems*,
619 11(8), 126.

620 Zheng, L., Lu, W., Chen, K., Chau, K. W., and Niu, Y. (2017). Benefit sharing for BIM
621 implementation: Tackling the moral hazard dilemma in inter-firm cooperation.
622 *International Journal of Project Management*, 35(3), 393-405.

623

624




625

626

627

628

Figure 1. System architecture of BBB



629

630

Figure 2. Deployment procedures of BBB

631

632

633

634

635

636

637

638


639

640

641

642

643



644

645

Figure 3. Workflow of the case project

646

647

648

649

650

651

652

653

654

655

656 Table 1 Sources of the operation data

Operation data		Source	
		Before the system implementation	After the system implementation
Production	Paper work (sheet/day)	Observation	Observation
	Production cycle (day)	Project documents	BBB system
	Working-in-process inventory (set)	Project documents	Observation
	Locating a component (min)	Observation	BBB system
Transportation	Paper work (sheet/car)	Observation	Observation
	Time for order picking (hour)	Observation	BBB system
	Waiting time for delivery (hour)	Observation	BBB system
On-site assembly	Recording the installation (min/wing)	Observation	BBB system
	Locating a component (min)	Observation	BBB system
	Accuracy rate of on-site assembly (%)	Project documents	BBB system

657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681

682 Table 2 List of interviewees

	Interviewee	Identification code
Company A (Prefabrication factory)	Worker 1	WW1
	Worker 2	WW2
	Manager	WM
Company B (Third-party logistics company)	Driver 1	YD1
	Driver 2	YD2
	Manager	YM
Company C (Main contractor)	Worker 1	GW1
	Worker 2	GW2
	Manager 1	GM1
	Manager 2	GM2

683

684

685

686

687

688

689

690

691

692

693

694

695

696

697

698

699

700 Table 3 Key feedback from interviewees

Type	Interviewee	Feedback
Manager	WM	By adopting the BBB system, information of components could be real-time traced and automatically recorded in the database
	YM	By using the BBB system, the transportation planning and scheduling of our company are facilitated as accurate information about locations and status of delivery tasks could be obtained
	GM1	The BBB system enables real-time information visibility and traceability through a BIM-based approach and seamless collaboration and obstacle-free communications among partners
	GM2	The BBB system allows me to perform real-time monitoring on the components projection, logistics, and the installation. The system allows viewing relevant information of the whole process by simply clicking. It achieves some innovative solutions. For example, I can review the BIM model to check whether a precast façade is installed on the right place
Worker	WW1	It is easy for me to view the up-to-date production tasks assigned to me in the smartphone app
	WW2	I can rely on details of a prefabricated component shown in the smartphone app to conduct production. Before carrying out the production work, I can open the smartphone app to identify the components to be produced. After identifying the correct components, I can use the reader to scan the RFID tag for record
	YD1	The BBB system presented the information of truck and trailer assigned to me in a concise manner.
	YD2	It is not difficult to view the tasks in the smartphone app, and I can get instant response about whether the right transportation task is delivered.
	GW1	I feel that the confirmation of the on-site assembly work is faster than traditional methods
	GW2	I can view the result of task delivery in the single page of the smartphone app

701